

**राष्ट्रीय बीज निगम लिमिटेड,
केन्द्रीय राज्य फार्म, 10 कि०मी० सिरसा रोड, हिसार**

निविदा आमंत्रण सूचना

राष्ट्रीय बीज निगम लिमिटेड द्वारा प्रतिष्ठित ठेकेदारों को कि केन्द्रीय लोक निर्माण विभाग, एम.ई.एस. डाक एवं तार, राज्य/अर्धसरकारी संगठन के साथ पंजीकृत हो और इस प्रकार के कार्य निष्पादन में दक्षता रखते हो, और लेबर के लिए ई.पी.एफ. व ई.एस.आई. से पंजीकृत हो, से मद दर पर खुली निविदा आमंत्रित की जाती है।

क्र. सं०	कार्य का नाम	अनुमानित लागत डी.एस.आर.-13 के आधार पर रु० लाख	कार्य पूरा करने की अवधि	धरोहर राशि	निविदा दस्तावेज की लागत	निविदा दस्तावेज खुलने की तिथि व समय
1	दुर्जनपुर माईनर के आर. डी. 8220 आर पर फार्म के लिए बने खाले में आर.सी.सी.पाईप लाईन बिछाने का कार्य	9.19	1.5 माह	रु० 27,600	रु० 500/-	03.03.2016 दोपहर 3.00 बजे

नियम व शर्तें किसी भी कार्य दिवस पर कार्यालय समय में देखी जा सकती हैं।

कृते: उप-महाप्रबंधक (फार्म)

राष्ट्रीय बीज निगम लिमिटेड

केन्द्रीय राज्य फार्म: हिसार

Phones: (91)1662-275581, 275797

No. CSF/6-70/SBW/Agri./2016/

Dated: 10-2-2016

NATIONAL SEEDS CORPORATION LIMITED
(A GOVT. OF INDIA UNDERTAKING MINIRATNA COMPANY)
CENTRAL STATE FARM
HISAR:125001

NOTICE INVITING TENDER

National Seeds Corporation Ltd. (NSC) ,invites item rate sealed tenders(two bid system1.Technical 2.Finincial), from reputed Contractors Registered in appropriate class with CPWD/PWD/Municipal Authorities/Semi Govt. Organization and having executed the similar kind of work & who are having EPF & ESI Registration for Labours.

Name of work	Estimated Cost (in lakh)	Period of completion	Earnest money (Rs.)	Cost of tender document (Rs.)
Laying of RCC pipe line in water course of farm at 8220 RD/R of Durjanpur minor	9.19	1.5 months	27600/-	500/-

1. Tender document may be obtained from the central state farm Hisar on any working day on payment of cost of tender Rs. 500/- (non refundable) on or before 01/03/2016 upto 5:00pm through cash/Bank draft in favor of NSC Ltd., Hisar.
2. Earnest money mentioned above should be accompanied with the tender in the shape of DD drawn on any Nationalized Bank payable at NSC, hisar.
3. Tender shall be received in two envelopes i.e one for technical & 2nd for financial bid on 03.03.2016 up to 13.00 hours at central state farm, NSC, Ltd, Hisar and technical bid will be opened on the same day at 15.00 hours in presence of tenderer who wish to attend. Financial bids will be opened after evaluating of technical bids and it will be intimated on phone or by mail.
4. Change in terms and conditions or the specifications & schedule of completion shall not be accepted. Such conditional tenders are liable for rejection.
5. The Corporation reserves the right to accept or reject any/all tenders without assigning any reason whatsoever and decision of the Corporation shall be final and binding on tenderer.
6. Cement will be issued by the farm @Rs 262/- per bag.
7. A pre bid meeting will be held for giving any explanation on the issue on 02.03.2016 at 11.00 am.

CENTRAL STATE FARM: HISAR.

Name of work: Laying of Rcc pipe line in water course of farm at 8220RD/R of Durjanpur
Minor

Schedule of Quantity

Sr. No.	Description	Qty.	Unit	Rate	Amount
1.	Providing and Laying non pressure NP2 class (light duty) R.C.C pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement:2 fine sand) including testing of joints etc. complete: 300mm dia R.C.C. pipe. (code no. 19.6.4 Page no. 350)	1040.00	mtr.		
2.	Earch work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30cm in depth. 1.5m in width as well as 10sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earch to be levelled and neatly dressed. All kinds of soil. (Code no. 2.6.1 Page no. 72)	1581.20	cum		
3.	C.C. 1:4:8 (1cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size) under bed of chambers. (Code no. 4.1.8 Page no. 85)	3.395	cum		
4.	Brick on edge flooring with bricks of class designation 7.5 on a bed of 12mm cement mortar including filling the joints with same mortar with common burnt clay non modular bricks: 1:4 (1cement : 4 coarse sand) (Code no. 11.1.1 Page no. 186) Chamber	28.20	sqm		
5.	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1cement : 4 coarse sand) (code no. 6.1.1 Page no. 111) Chamber	20.18	cum		
6.	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of	1.77	cum		

	centering, shuttering, finishing and reinforcement-All work up to plinth level: 1:2:4 (1cement : 2coarse sand : 4 graded stone aggregate 20mm nominal size.) (Code no. 5.1.3)				
7.	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars. (Code no. 5.22.1 Page no. 99)	200	kg		
8.	15mm cement plaster 1:3 (1cement : 3 coarse sand) finished with a floating coat of neat cement on the rough side of single or half brick wall. (code no. 13.10 Page no. 222)	77.42	sqm		
9.	Providing and fixing of M.S. angle iron steps for going into chamber in C.C. 1:2:4 (N.S. item)	20	nos.		