राष्ट्रीय बीज निगम लिमिटेड
(भारत सरकार का उपक्रम-
मिनिरत्न कम्पनी)
बीज भवन, पूसा परिसर
नई दिल्ली -110 012
फैक्स- 011- 25846462
केन्द्रीय राज्य फार्म, सरदारगढ़ (राज.)
फैक्स-01509-238027

NATIONAL SEEDS CORPORATION LIMITED
(A Government of India Undertaking)
(CIN : U74899DL1963PLC003913)
BEEJ BHAWAN, PUSA COMPLEX
NEW DELHI-110 012 (INDIA)
Website: www.indiaseeds.com
PHONES : 25842383, 25846272, 25842692, 25846295
e-mail – nsc@indiaseeds.com
CENTRAL STATE FARM, SARDARGARH
PHONES: 01509-238027, 238296 (Office)
Tele – Fax :- 01509-238027
e-mail – directorcsfsrg@gmail.com

No:- CSF/SRG/CIVIL/48 /2015-16

Dated 26.02.2016

TENDER NOTICE

1. The Director Central State Farm, Sardargarh invites bids for the construction of works detailed in the table given in para-7 here in after. The bidders may submit bids for any or all of the works.

2. Bidding is open to all eligible bidders meeting the eligibility criteria as defined in clause No. 3.5 of instructions to Bidders should, however, be registered with Central Govt./State Govt. or Central/State Undertakings, Bidders are advised to note the minimum qualification criteria specified in clause 4 of the instructions to bidders to qualify for the award of the contract.

3. Bidding documents (and additional copies) may be purchased from the office of the Asstt. Manager (Civil) from **29/02/2016 to 21/03/2016** during office hours for a non-refundable fee as indicated; in the form of cash or Demand Draft on any scheduled bank payable at **SURATGARH (Raj.)** in favour of **NATIONAL SEEDS CORPORATION LIMITED, SARDARGARH.**

   Interested bidders may obtain further information at the same address. Bidding documents requested by mail will be dispatched by Registered/speed post on payment of an extra amount of ₹100/- (Rupees one hundred only). The Management will not be held responsible for the postal delay if any, in the delivery of the documents of non-receipt of the same.

4. Bids must be accompanied by security amount specified for the work in the table below, payable at SURATGARH (Raj.) drawn in favour of NATIONAL SEEDS CORPORATION SARDARGARH. Bid security will have to be in any one of the forms as specified in the bidding documents and shall have to be valid for 28 days beyond the validity of the bid.

5. Bids must be delivered to the DIRECTOR, CENTRAL STATE FARM, SARDARGARH – 335705 (RAJ.) on or before 1100 hours on **22/03/2016** and technical bid will be opened on the same day at 1200 hours and Financial bid will be opened at 1500 hours in the presence of the bidders who wish to attend. If the office happens to be closed on the date of receipt of the bids as specified the bids will be received and opened on the next working day at the same time and venue.

-Continued on Page No. 2-

6. A pre bid meeting will be held on **21/03/2015 at 1700 hours** at the office of ASSTT MANAGER (CIVIL) TO CLARIFY THE ISSUES AND TO ANSWER QUESTIONS ON ANY MATTER THAT MAY BE RAISED AT THAT STAGE AS STATED IN clause 9.2 of Instructions to Bidders of the Bidding documents.

7. Other details can be seen in the bidding documents.

S.No.	Name of Work	Approximate value of Work (₹ in Lacs)	Bid Security (₹ in Lacs)	Cost of Documents (in ₹)	Period of completion
1.	Construction for Lining of Water Course 1.10 Kms length.	30.70	1.00	1500.00	60 Days

TECHNICAL BID:- EMD D.D., Copies of Firm registration, EPF & ESI Registration, Sales Tax Clearance, Service tax registration, Experience and Pan Card must be enclosed in Technical Bid.

FINANCIAL BID:- Rates should be inclusive of all taxes & unconditional.

Note:-

i) Cement will be issued from the General Store of Farm.
ii) Any type of tax liability of government will be borne by the contractor.
iii) Number of items & quantities of any item may increase or decrease.
iv) If any additional works are required to be executed, the contractor has to execute in the same proportionate rate quoted by him.
v) The work experience for the contractor/ firm should be 40% of three work or 50% of two works or 80% of one work of similar nature during last seven years.
vi) Any Tools & Plants will be arranged by the contractor.
vii) Insurance of labour working at site should be done before start of work.
viii) Canal water is to be used for construction of work.

DGM (Farm)
CSF Sardargarh

NATIONAL SEEDS CORPORATION LIMITED

(A Govt. of India Undertaking)

CENTRAL STATE FARM :- SARDARGARH (Raj.)

RATES ARE WITHOUT CEMENT

G.SCHEDULE FOR CONSTRUCTION FOR LINING OF WATER COURSE FOR 1.10 KM LENGTH

SR. NO.	ITEM OF WORK	QTY.	UNIT	RATE	AMOUNT
1	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15cm deep and disposal of rubbish lead up to 50mtr and lift upto 1.5mtr. Ref. 2.28 (DSR-2014)	11000.00	SQM	12.45	**136950.00**
2	Earth work excavation in foundation trenches or drains not exceding 1.5 Mtr. in width or 10 SQM. On plan including dressing of side & ramming of bottoms, lift upto 1.5 Mtr. Including getting out the excavated soil & disposal of surplus excavated soil as directed within a lead of 50Mtr. Ref. 2.8.1 (DSR-2014)	554.40	CUM	157.5	**87318.00**
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) Ref 4.1.8 DSR 2014	9.98	CUM	3230.15	**32236.90**
4	Providing 250 micron LDPE film as per ISS 2508-1984 and laying it properly including overlapping as per ISS over finished and excavated earth surface, 10cm tibba sand in two layers properly watered and rammed shall be laid over complete. The film shall be laid (LDPE) over 15mm thick cement Bajri mortar. 1:3 and single layers of Ist class brick masonry in cm 1:3 with the filling of joints not more than 8mm, and the curing will have to be done for 28 days minimum. This work will also include providing vedicides and anti-termite treatment as per specification **(item of public health engineering department) BSR 2012.**	1885.50	SQM	295.85	**557825.18**
5	Brick work with bricks of class designation 75 in Foundation and plinth in cement mortar 1:6 (1Cement : 6 Course Sand) Ref. 6.1.2 (DSR-2014)	321.85	CUM	4283.50	**1378644.48**
6	20 MM Cement plaster on new surface on walls in cement sand mortar of Mix : 1:6 (1Cement : 6 Course Sand) including racking of joint etc complete Ref. 13.6.2 (DSR-2014)	1034.00	SQM	185.12	**191414.08**

NATIONAL SEEDS CORPORATION LIMITED

(A Govt. of India Undertaking)

CENTRAL STATE FARM :- SARDARGARH (Raj.)

RATES ARE WITHOUT CEMENT

G.SCHEDULE FOR CONSTRUCTION FOR LINING OF WATER COURSE FOR 1.10 KM LENGTH

7	12 MM Cement plaster on new surface on walls in cement sand mortar of Mix : 1:6 (1Cement : 6 Course Sand) including racking of joint etc complete Ref. 13.4.2 (DSR-2014)	3273.12	SQM	135.72	**444227.85**
8	Providing and laying 450 mm non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete. Ref. 19.6.5 (DSR-2014)	40.00	RM	690.78	**27631.20**
9	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.. Ref. 10.1 (DSR-2014)	300.00	kg	67.7	**20310.00**
10	Filling With avialable earth (excluding rock) in trenches or in plinth sides of foundations etc in layers not exceeding 20cm in depth consolidating each layer by ramming watering lead upto 50m and lift upto 1.5m. Ref. 2.25 (DSR-2014)	1728.10	CUM	112.40	**194238.44**
	TOTAL				**3070796.11**
	G.schedule Amount				**3070796.11**

Terms & Conditions

1.. **Rate Should be inclusive of all taxes and unconditional.**
2.. Any type of tax liability of government will be borne by the contractor.
3.. All the tools and plants will be arranged by the contractor.
4.. No. of above items & respective quantity may increase or decrease.
5.. If any additional works are requied to be executed, the contractor has to execute in the same proportionate rate quoted by him.
6.. Cement will be provided from the general store of the farm.
7.. Insurance of labour working at site will be done by the contractor.
8.. For all construction works strictly canal water is to be used at site.

Rate quoted by contractor _____% Above on G. schedule amount

Rate quoted by contractor _____% Below on G. schedule amount

Name and Signature
Contractor