



NATIONAL SEEDS CORPORATION LIMITED

(A Government of India Undertaking)

Regional Office, Chennai

No:7(2)Engg/NSC/CHN/2013-14

Date:03.03.2014

CORRIGENDUM(IT-990)

This is continuation of this office tender IT. No.990 dated 27.02.2014 for construction of sun drying platform at palakkad. The schedule of quantity for the construction of sun drying platform has been changed & revised schedule is enclosed & the same may be used for submission of tender. Other terms & condition remains unchanged.

Regional Manager

Schedule of quantity for the construction of Sun drying platform of size 15m x 15m as per site condition of Palakkad.

S.N.	Ref.of item code	Description of item	Quantity	Unit	Rate in Rs.	Amount Rs.
1	2.8.1	Earth work in excavation by mechanical means/manual in foundation trenches or drain, dressing of sides and ramming of bottoms, lift up to 1.5m including getting out the excavated soil and disposal of surplus excavated soil as directed	27.00	Cum		
2	4.1.10	Providing and laying in position cement concrete of specified grade 1:5:10 (1 cement : 5 coarse sand: 10 graded stone agg.)	25.00	Cum		
3	6.2.2	Brick work with bricks of class designation 75 in cement mortar 1:6 (1 Cement: 6 coarse sand) in foundation and plinth.	52.00	Cum		
4	4.1.3	Providing and laying cement concrete 1:2:4(1 cement: 2 coarse sand : 4 graded stone agg. 12.5 mm nominal size) in panels not exceeding 2.50 sqm area up to plinth under floor including top finished smooth.	16.88	Cum		
5	13.5.2	15mm thick plaster with cement mortar 1:6 (1 cement : 6 coarse sand) up to the plinth height.	60	Sqm		
6	16.3.9	Supplying and filling good earth in plinth under floor etc. in layers not exceeding 20 cm in depth , consolidating each deposited layerby ramming and watering ,lead upto 50 m and lift upto 1.50 m.	63.08	Cum		
7	2.27	Supplying and filling plinth with local sand under floors including ramming and watering ,consolidating and dressing complete.	21.03	Cum		
		G.Total				

Note:- The rate shall includes all materials, labours, tools and plants up to requisit hight and depth for the finished work.