



NATIONAL SEEDS CORPORATION LIMITED

A Govt. of India Undertaking – “Mini Ratna” Company

Central State Farm, Sardargarh

Distt. Sri Ganganagar (Raj.)
☎- 01509-238027, 238296 (Office)
Fax: 01509- 238027 (Office)

No. CSF/SRG/Civil/10A/2014-15/

Dated: 30.07.2014

TENDER NOTICE

1. The Central State Farm, Sardargarh invites bids for the construction of works detailed in the table given in para-7 here in after. The bidders may submit bids for any or all of the works.
2. Bidding is open to all eligible bidders meeting the eligibility criteria as defined in clause No. 3.5 of instructions to Bidders should, however, be registered with Central Govt. /State Govt. or Central/State Undertakings, Bidders are advised to note the minimum qualification criteria specified in clause 4 of the instructions to bidders to qualify for the award of the contract.
3. Bidding documents (and additional copies) may be purchased from the office of the Manager Engineer (Civil) from 01.08.14 to 25.08.14 during office hours for a non-refundable fee as indicated; in the form of cash or Demand Draft on any scheduled bank payable at SURATGARH (Raj.) in favor of NATIONAL SEEDS CORPORATION LIMITED.

Interested bidders may obtain further information at the same address. Bidding documents requested by mail will be dispatched by Registered/speed post on payment of an extra amount of Rs. 100/- (Rupees one hundred only). The Management will not be held responsible for the postal delay if any, in the delivery of the documents of non-receipt of the same.

4. Bids must be accompanied by security amount specified for the work in the table below, payable at SURATGARH (Raj.) drawn in favor of NATIONAL SEEDS CORPORATION LIMITED.
 - . Bid security will have to be in any one of the forms as specified in the bidding documents and shall have to be valid for 28 days beyond the validity of the bid.
5. Bids must be delivered to the DIRECTOR, CENTRAL STATE FARM, SARDARGARH – 335805 on or before 1100 hours on 26.08.14 and technical bid will be opened on the same day at 1200 hours and financial bid will be opened at 1500 hours in the presence of the bidders who wish to attend. If the office happens to be closed on the date of receipt of the bids as specified the bids will be received and opened on the next working day at the same time and venue.

Contd...2---

6. A pre bid meeting will be held on 25.08.2014 at 1700 hours at the office of MANAGER ENGINEER (CIVIL) TO CLARIFY THE ISSUES AND TO ANSWER QUESTIONS ON ANY MATTER THAT MAY BE RAISED AT THAT STAGE AS STATED IN clause 9.2 of Instructions to Bidders of the Bidding documents.
7. Other details can be seen in the bidding documents.

Sr. No.	Name of Work	Approximate value of work	Bid security	Cost of documents (In Rs)	Period of completion
		Rs. (in Lacs.)			
1	Construction of Deep tube well at Sardargarh farm (04 No.)	26.00	0.80	1500.00	60 days

Note:

1. Cement will be issued from the general store of the farm.
2. Number and quantity of Work may increase or decrease.
3. No time extension will be given for execution of work.
4. Canal water is to be used for construction work.
5. Rates should be inclusive of all type of govt. taxes.
6. If any additional item is required to be executed the contractor has to execute in the same proportionate rate quoted by him.
7. The contractor/firm has to be registered for civil construction works.
8. The work experience for the contractor should be 40% of three work or 50% of two works or 80% of one work of similar nature during last seven years.

Manager (Engg-Civil)
For Director



NATIONAL SEEDS CORPORATION LTD

(A Govt. of India Undertaking- "Mini-Ratna" Company)

CENTRAL STATE FARM :- SURATGARH (Raj.)

RATES ARE WITHOUT CEMENT

G.SCHEDULE FOR CONSTRUCTION OF RCC CULVERT					
SR. NO.	ITEM OF WORK	QTY.	UNIT	RATE	AMOUNT
1	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.5 m. Code No.- 2.28 (Page No. 75), DSR, CPWD 2013	107.28	SQM	11.24	1205.83
2	Earth work by mechanical means (Hydraulic excavation)/manual means in foundation trenches or drains (not exceeding 1.5 mtr in width or 10 sqm on plan), including dressing of side & ramming of bottoms, lift upto 1.5 mtr, including getting out the excavated soil & disposal of surplus excavated soil as directed, within a lead of 50mtr. All Kinds of soils. Code No - 2.8.1, (Page No. 72) DSR, CPWD 2013	155.02	CUM	148.25	22981.72
3	Providing & laying cement concrete 1:5:10 in footing & bases for columns, excluding the cost of centring & shuttering. Code No. - (4.1.10) (Page No. 85), DSR, CPWD 2013	10.54	CUM	2957.80	31175.21
4	52 mm thick cement concrete flooring with concrete hardener topping, under layer 40 mm thick cement concrete 1:2:4 (1 cement : 2 Coarse sand : 4 graded stone aggregate 20 mm nominal size) and top layer 12 mm thick cement hardener consisting of mix 1:2 (1 cement hardener mix : 2 graded stone aggregate 6 mm nominal size) by volume, hardening compound mixed @ 2 litre per 50 kg of cement or as per manufacture's specifications. This includes cost of cement slurry, but excluding the cost of nosing of steps etc, complete. Code No - 11.4, (page No. 186), DSR, CPWD 2013	22.06	SQM	353.05	7788.28
5	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand) Code No.- (6.1.2) (Page No. 111), DSR, CPWD 2013	18.61	CUM	4302.75	80074.18
6	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1Cement : 6 Course Sand) Code No. - 6.4.2 (Page No. 111), DSR, CPWD 2013	17.57	CUM	4981.35	87522.32
7	12 MM Cement plaster of Mix : 1:6 (1Cement : 6 Course Sand) Code No. - 13.4.2 (Page No. 222) DSR, CPWD 2013	98.34	SQM	122.45	12041.73
8	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up to floor five level, excluding cost of centring, shuttering finishing and reinforcement : 1:2:4 (1 cement :2 course sand : 4 graded stone aggregate 20 mm nominal size) Code No.- 5.2.3 (Page No. 96), DSR, CPWD 2013	3.24	CUM	4163.15	13488.61
9	Centring and shuttering including strutting, propping and removal of form work for : Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps et. Code No.- 4.3.2 (Page No. 86), CSR, CPWD 2013	18.15	SQM	334.50	6071.18



NATIONAL SEEDS CORPORATION LTD

(A Govt. of India Undertaking- "Mini-Ratna" Company)

CENTRAL STATE FARM :- SURATGARH (Raj.)

RATES ARE WITHOUT CEMENT

G.SCHEDULE FOR CONSTRUCTION OF RCC CULVERT					
SR. NO.	ITEM OF WORK	QTY.	UNIT	RATE	AMOUNT
10	Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars. Code No.- 5.22.6 (Page No. 99), DSR, CPWD 2013	500.40	KG	66.50	33276.60
	TOTAL				295625.65
	GRAND TOTAL FOR THREE (03) NO's OF CULVERTS = 2,95,625.65 Lacs x 3 no's				886876.94

Terms & Conditions

1. All the tools and plants will be arranged by the contractor.
2. All the risk of labour working at site will be covered by the contractor.
3. The work will be completed within 45 days from the date of work order issued.
4. Quantity may increase or decrease.
5. Cement will be provided from the general store of the farm.
6. For all construction works strictly canal water is to be used at site.

Rate quoted by contractor _____ % Above on G. schedule amount

Rate quoted by contractor _____ % Below on G. schedule amount

**Name and Signature of
Contractor**



NATIONAL SEEDS CORPORATION LTD

(A Govt. of India Undertaking- "Mini-Ratna" Company)

CENTRAL STATE FARM :- SURATGARH (Raj.)

RATES ARE WITHOUT CEMENT

G.SCHEDULE FOR CONSTRUCTION OF RCC HUME PIPE SYPHONE IN FARM MINOR

SR. NO.	ITEM OF WORK	QTY.	UNIT	RATE	AMOUNT
1	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.5 m. Code No.- 2.28 (Page No. 75), DSR, CPWD 2013	22.50	SQM	11.24	252.90
2	Earth work by mechanical means (Hydraulic excavation)/manual means in foundation trenches or drains (not exceeding 1.5 mtr in width or 10 sqm on plan), including dressing of side & ramming of bottoms, lift upto 1.5 mtr, including getting out the excavated soil & disposal of surplus excavated soil as directed, within a lead of 50mtr. All Kinds of soils. Code No - 2.8.1, (Page No. 72) DSR, CPWD 2013	124.80	CUM	148.25	18501.60
3	Providing & laying cement concrete 1:5:10 in footing & bases for columns, excluding the cost of centring & shuttering. Code No. - (4.1.10) (Page No. 85), DSR, CPWD 2013	5.40	CUM	2957.80	15972.12
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand) Code No.- (6.1.2) (Page No. 111), DSR, CPWD 2013	12.33	CUM	4302.75	53052.91
5	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1Cement : 6 Course Sand) Code No. - 6.4.2 (Page No. 111), DSR, CPWD 2013	1.31	CUM	4981.35	6525.57
6	12 MM Cement plaster of Mix : 1:3 (1 Cement : 3 Course Sand) Code No. - 13.9.1 (Page No. 222) DSR, CPWD 2013	23.20	SQM	148.13	3436.62
7	52 mm thick cement concrete flooring with concrete hardener topping, under layer 40 mm thick cement concrete 1:2:4 (1 cement : 2 Coarse sand : 4 graded stone aggregate 20 mm nominal size) and top layer 12 mm thick cement hardener consisting of mix 1:2 (1 cement hardener mix : 2 graded stone aggregate 6 mm nominal size) by volume, hardening compound mixed @ 2 litre per 50 kg of cement or as per	27.00	SQM	353.05	9532.35
8	Providing and laying Non Pressure NP-3 class (Medium duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 Cement : 2 fine sand) including testing of joints etc. complete. 19.35.1 450mm dia RCC pipes (Page No. 357) DSR, CPWD 2013	24.00	MTR	1799.55	43189.20
9	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50m and lift upto 1.5m. Adding extra for every lift of 1.5m or part thereof in excavation/banking excavated or stacked materials. All kind of soils. Code No. - 2.25 & 2.26.1 (Page No. 75), DSR, CPWD 2013	96.00	SQM	334.50	32112.00
TOTAL					182575.26

Terms & Conditions

1. All the tools and plants will be arranged by the contractor.
2. All the risk of labour working at site will be covered by the contractor.
3. The work will be completed within 45 days from the date of work order issued.
4. Quantity may increase or decrease.
5. Cement will be provided from the general store of the farm.
6. For all construction works strictly canal water is to be used at site.

Rate quoted by contractor _____ % Above on G. schedule amount

Rate quoted by contractor _____ % Below on G. schedule amount

**Name and Signature of
Contractor**