

NATIONAL SEEDS CORPORATION LIMITED;
REGIONAL OFFICE: SECUNDERABAD

No: Engg/Civil/NSC-HYD/2014-15/
To

Dated: 10.10.2014

Sir,

Sub:- Quotation for Repair of Roof Leakage for A.C., Non-A.C. Seed Store & Generator Room at NSC, Lalaguda

DETAILS OF WORK

S.N O	DESCRIPTION	QUAN- TITY	Rate quotedPer Job
1.	Dismantling Tar Felt from TOP surface of Roof and Sides of inverted beam and removing debris outside the premises.	181.24 Sq.m.	
2.	Dismantling old plaster Average "2 thick over RCC Roof of A.C., Non-A.C. Seed Store and Generator Room racking out joints and cleaning the surface and removing debris outside of premises.	585.00 Sq.m.	
3.	Providing and laying in position ready mixed plain cement concrete over Rcc Slab of A.C.,Non-AC Seed Store & Generator Room average 2 "½ thick using fly ash and cement content as per approved design mix and manufactured in fully automatic machine Plant and transported to site of work in transit mixing for all leads,having continuous agitated mixer manufactured as per mix design of specified grade for plain cement concrete work, including pumping of RMC from transit mixer to site of laying and curing, excluding the cost of centring, shuttering and finishing, including cost of curing admixtures in recommended proportion. As per IS:9103 to Accelerate/Retard setting of concrete improve workability without impairing strength and durability as per direction of Engineer-in-charge. Excess /less cement used than specified is payable/recoverable. 4.19.2.1 M-15 Cement 240 kg./M3	36.41 cu.m.	
4.	Repair to Plaster 12 mm to 20 mm in patches of area 2.50 Sq.m.including cutting the patch Raking out joints and preparing and plastering the surface of wall including disposal of rubbish to dumping ground within 50 Mtr. 4.1.1 with cement mortar 1:4 . Ceiling of Guest Room on First Floor VPC(S) Office. Outer Wall of Storage Godown.	13.5 sq.m	

TERMS & CONDITIONS:-

1. Sealed quotations are invited from Contractors who are having experienced of civil constructions works of minimum 2 years.
2. The work has to be executed as per specifications and quantities are mentioned against each item. The contractor has to quote his rate for One job i.e. for sl.no. 1 to 4 including curing.
3. The work has to be executed as per satisfaction of NSC.
4. The rate has to be quoted inclusive of all taxes applicable.
5. Security Deposit will be deducted 10% and same will be released after a period of 6 months.
6. Entire work has to be completed within 21 days from the date of issue of work order.
7. The last date for submission of quotation is 20.10.2014 at 3.00 p.m., same will be opened on same day at 3.30 P.M.

REGIONAL MANAGER