



राष्ट्रीय बीज नि लि
(भारत सरकार का उपत्र - मिनि कम्)
केन्द्रीय राज्य फार्म, सूरतगढ़
जिला - श्रीगंगानगर (राजो)
फैक्स - 01509 - 223877
दूरभाष : 01509-220084,220068

NATIONAL SEEDS CORPORATION LIMITED
(A Government of India Undertaking)
(CIN : U74899DL1963PLC003913)

Central State Farm, Suratgarh

PHONES : 01509-220084,220068

"An ISO 9001:2008 & ISO 14001:2004 Company"

e-mail – csfsuratgarh@rediffmail.com

Website: www.indiaseeds.com

No. CSF/SOG/4-1(15)/2014-15

Dated: 21.03.2015

TENDER NOTICE

1. The Central State Farm, Suratgarh invites bids for the construction of works detailed in the table given in para-7 here in after. The bidders may submit bids for any or all of the works.
2. Bidding is open to all eligible bidders meeting the eligibility criteria as defined in clause No. 3.5 of instructions to Bidders should, however, be registered with Central Govt. /State Govt. or Central/State Undertakings, Bidders are advised to note the minimum qualification criteria specified in clause 4 of the instructions to bidders to qualify for the award of the contract.
3. Bidding documents (and additional copies) may be purchased from the office of the Manager Engineer (Civil) from 24.03.2015 to 18.04.2015 during office hours for a non-refundable fee as indicated; in the form of cash or Demand Draft on any scheduled bank payable at **SURATGARH** (Raj.) in favor Of **NATIONAL SEEDS CORPORATION LIMITED SURATGARH**.

Interested bidders may obtain further information at the same address. Bidding documents requested by mail will be dispatched by Registered/speed post on payment of an extra amount of ₹. 100/- (Rupees one hundred only). The Management will not be held responsible for the postal delay if any, in the delivery of the documents of non-receipt of the same.

4. Bids must be accompanied by security amount specified for the work in the table below, payable at SURATGARH (Raj.) drawn in favor of NATIONAL SEEDS CORPORATION LIMITED SURATGARH.
Bid security will have to be in any one of the forms as specified in the bidding documents and shall have to be valid for 28 days beyond the validity of the bid.
5. Bids must be delivered to the DIRECTOR, CENTRAL STATE FARM, SURATGARH – 335804 on or before 1100 hours on 20.04.2015 and technical bid will be opened on the same day at 1200 hours and financial bid will be opened at 1500 hours in the presence of the bidders who wish to attend. If the office happens to be closed on the date of receipt of the bids as specified the bids will be received and opened on the next working day at the same time and venue.

Contd...2---

: 2 :

6. A pre bid meeting will be held on 18.03.2015 at 1700 hours at the office of MANAGER ENGINEER (CIVIL) TO CLARIFY THE ISSUES AND TO ANSWER QUESTIONS ON ANY MATTER THAT MAY BE RAISED AT THAT STAGE AS STATED IN clause 9.2 of Instructions to Bidders of the Bidding documents.
7. Other details can be seen in the bidding documents.

Sr. No.	Name of Work	Approximate value of work	Bid security	Cost of documents (In ₹.)	Period of completion
		₹. (in Lacs.)			
1.	Construction of Water Course at 42 STG Suratgarh farm (1.30 Km Length)	27.10	0.85	1000.00	60 days
1.	Construction of Water Course at 5SGM Suratgarh farm (2.00 Km Length)	45.27	1.40	2000.00	75 days

Note:

1. Cement will be issued from the general store of the farm.
2. Number and quantity of Work may increase or decrease.
3. No time extension will be given for execution of work.
4. Canal water is to be used for construction work.
5. Rates should be inclusive of all type of govt. taxes.
6. If any additional items are required to be executed the contractor has to execute in the same proportionate rate quoted by him.
7. The contractor/firm has to be registered for civil construction works.
8. The work experience for the contractor should be 40% of three work or 50% of two works or 80% of one work of similar nature during last seven years.

Manager (Engg-Civil)
For Director



NATIONAL SEEDS CORPORATION LIMITED

(A Govt. of India Undertaking)

CENTRAL STATE FARM :- SURATGARH (Raj.)

RATES ARE WITHOUT CEMENT

G.SCHEDULE FOR CONSTRUCTION FOR LINING OF WATER COURSE FOR 1.3 KM LENGTH : AT 42 STG of BLOCK NO I					
SR. NO.	ITEM OF WORK	QTY.	UNIT	RATE	AMOUNT
1	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15cm deep and disposal of rubbish lead up to 50mtr and lift upto 1.5mtr. Ref. 2.28 (DSR-2013)	2860.00	SQM	11.25	32175.00
2	Earth work excavation in foundation trenches or drains not exceeding 1.5 Mtr. in width or 10 SQM. On plan including dressing of side & ramming of bottoms, lift upto 1.5 Mtr. Including getting out the excavated soil & disposal of surplus excavated soil as directed within a lead of 50Mtr. Ref. 2.8.1 (DSR-2013)	1560.00	CUM	148.25	231270.00
3	Providing 250 micron LDPE film as per ISS 2508-1984 and laying it properly including overlapping as per ISS over finished and excavated earth surface, 10cm tibba sand in two layers properly watered and rammed shall be laid over complete. The film shall be laid (LDPE) over 15mm thick cement Bajri mortar 1:3 and single layers of 1st class brick masonry in cm 1:3 with the filling of joints not more than 8mm, and the curing will have to be done for 28 days minimum. This work will also include providing vedicides and anti-termite treatment as per specification (item of public health engineering department) BSR 2012.	2210.00	SQM	295.85	653828.50
4	Brick work with bricks of class designation 75 in Foundation and plinth in cement mortar 1:6 (1Cement : 6 Course Sand) Ref. 6.1.2 (DSR-2013)	269.10	CUM	4302.75	1157870.03
5	20 MM Cement plaster on new surface on walls in cement sand mortar of Mix : 1:6 (1Cement : 6 Course Sand) including racking of joint etc complete Ref. 13.6.2 (DSR-2013)	1950.00	SQM	164.80	321360.00
6	12 MM Cement plaster on new surface on walls in cement sand mortar of Mix : 1:6 (1Cement : 6 Course Sand) including racking of joint etc complete Ref. 13.4.2 (DSR-2013)	2288.00	SQM	122.45	280165.60
7	Filling With avialable earth (excluding rock) in trenches or in plinth sides of foundations etc in layers not exceeding 20cm in depth consolidating each layer by ramming watering lead upto 50m and lift upto 1.5m. Ref. 2.25 (DSR-2013)	325.00	CUM	101.50	32987.50
TOTAL					2709656.63

Terms & Conditions

1. All the tools and plants will be arranged by the contractor.
2. Insurance of labour working at site will be done by the contractor.
3. Quantity of the work may increase or decrease.
4. Cement will be provided from the general store of the farm.
5. For all construction works strictly canal water is to be used at site.

Rate quoted by contractor _____ % Above on G. schedule amount

Rate quoted by contractor _____ % Below on G. schedule amount

**Name and Signature of
Contractor**



NATIONAL SEEDS CORPORATION LIMITED

(A Govt. of India Undertaking)

CENTRAL STATE FARM :- SURATGARH (Raj.)

RATES ARE WITHOUT CEMENT

G.SCHEDULE FOR CONSTRUCTION FOR LINING OF WATER COURSE FOR 2.0 KM LENGTH : AT 5SGM of BLOCK NO III					
SR. NO.	ITEM OF WORK	QTY.	UNIT	RATE	AMOUNT
1	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15cm deep and disposal of rubbish lead up to 50mtr and lift upto 1.5mtr. Ref. 2.28 (DSR-2013)	4000.00	SQM	11.25	45000.00
2	Earth work excavation in foundation trenches or drains not exceeding 1.5 Mtr. in width or 10 SQM. On plan including dressing of side & ramming of bottoms, lift upto 1.5 Mtr. Including getting out the excavated soil & disposal of surplus excavated soil as directed within a lead of 50Mtr. Ref. 2.8.1 (DSR-2013)	1360.00	CUM	148.25	201620.00
3	Providing 250 micron LDPE film as per ISS 2508-1984 and laying it properly including overlapping as per ISS over finished and excavated earth surface, 10cm tibba sand in two layers properly watered and rammed shall be laid over complete. The film shall be laid (LDPE) over 15mm thick cement Bajri mortar 1:3 and single layers of 1st class brick masonry in cm 1:3 with the filling of joints not more than 8mm, and the curing will have to be done for 28 days minimum. This work will also include providing vecicides and anti-termite treatment as per specification (item of public health engineering department) BSR 2012.	3444.26	SQM	295.85	1018984.32
4	Brick work with bricks of class designation 75 in Foundation and plinth in cement mortar 1:6 (1Cement : 6 Course Sand) Ref. 6.1.2 (DSR-2013)	561.51	CUM	4302.75	2416037.15
5	20 MM Cement plaster on new surface on walls in cement sand mortar of Mix : 1:6 (1Cement : 6 Course Sand) including racking of joint etc complete Ref. 13.6.2 (DSR-2013)	1915.98	SQM	164.80	315753.50
6	12 MM Cement plaster on new surface on walls in cement sand mortar of Mix : 1:6 (1Cement : 6 Course Sand) including racking of joint etc complete Ref. 13.4.2 (DSR-2013)	3745.60	SQM	122.45	458648.72
7	Providing and laying 300 mm non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete. Ref. 19.6.4 (DSR-2013)	20.00	M	488.3	9766.00
8	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.. Ref. 10.1 (DSR-2013)	150.00	kg	66.85	10027.50
9	Filling With avialable earth (excluding rock) in trenches or in plinth sides of foundations etc in layers not exceeding 20cm in depth consolidating each layer by ramming watering lead upto 50m and lift upto 1.5m. Ref. 2.25 (DSR-2013)	500.00	CUM	101.50	50750.00
TOTAL					4526587.20

Terms & Conditions

1. All tools and plants will be arranged by the contractor.
2. Quantity may increase or decrease.
3. Cement will be provided from the general store of the farm.
4. For all construction works strictly canal water is to be used at site.
5. Insurance of labour working at site will be done by the contractor before starting the work.

Rate quoted by contractor _____ % Above on G. schedule amount

Rate quoted by contractor _____ % Below on G. schedule amount

**Name and Signature of
Contractor**