

NATIONAL SEEDS CORPORATION LIMITED
(A GOVERNMENT OF INDIA UNDERTAKING)
REGIONAL OFFICE : 65, PANDARIBA
LUCKNOW-226004

No.: IV/Engg.(16-Hempur)/NSC-LKO/2014-15

Dated: 31.03.2015

TENDER NOTICE

National Seeds Corporation Limited (NSC) invites item rate sealed tenders from Contractors registered with CPWD, MES, P & T, etc, and State Departments or Central/State Semi Govt. Organizations having executed the similar kind of works.

Sl. No.	Name of work	Estimated cost based on DSR-2013	Period of completion	Earnest Money (Rs.)	Cost of tender document (Rs.)
1.	Electrical work at newly constructed 'U' & 'L' shape stores at NSC, Hempur.	4,98,500/-	One Month	10,000/-	200/-

- 1- Tender document may be obtained from the Area Manager, PO - R.T.C., Hempur Distt. Udham Singh Nagar - 244716 (Uttarakhand) or Regional Office located at above mentioned address on any working day on payment of cost of tender (non refundable) on or before 16.04.2015 through cash/Nationalized Bank draft in favour of NSC Ltd., Lucknow. It may be downloaded from website of NSC www.indiaseeds.com. In such case a demand draft of Rs. 200/- is to be enclosed with tender as cost of tender documents.
- 2- Earnest money mentioned above should be accompanied with tender in the shape of DD drawn on SBI or any Nationalized Bank payable at NSC, Lucknow.
- 3- Tender shall be received on 17.04.2015 upto 14:00 hours at Area Office, PO - R.T.C., Hempur Distt. Udham Singh Nagar - 244716 (Uttarakhand) and shall be opened on the same day at 14:30 hours in presence of tenderer who wish to attend.
- 4- Change in terms and conditionals or specifications or schedule of completion shall not be accepted. Such conditional tender shall be liable for rejection.
- 5- Party shall be required to furnish copy of Registration, Pan and Income Tax return of previous year.
- 6- The Corporation reserves the right to accept or reject any or all tenders without assigning any reason what so ever and decision of the Corporation shall be final and binding on tenderers.

Regional Manager

TERMS AND CONDITIONS

1. Rates should be quoted in schedule of work in figures as well as in words and amount tendered by party.
2. Tender shall remain open for acceptance for a period of 90 days from the date of tender.
3. The unsealed & conditional tenders are liable to be summarily rejected.
4. Cutting/over writing in the offer must be avoided as may lead to cancellation of tender.
5. Scope of work according to situation may be increased or decreased without assigning any reason by Corporation.
6. For assigning work no extra amount will be paid to party in case he visits the site for surveying.
7. Deduction on payment will be governed according to rules.
8. Terms and conditions from Sl. No. 1 to 7 will be treated a part of order/contract.
9. Tax Liability :- Tax if any will be borne by the tenderer.

Signature and Seal of Party

NATIONAL SEEDS CORPORATION LIMITED, LUCKNOW

SCHEDULE OF QUANTITIES

Name of work : Electrification work of 65,000 quintals capacity stores at NSC, Hempur.

Sl. No.	Description of Work	Qty.	Unit	Rate	Amount in figure & words
1	Wiring for light point/fan point/exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface/recessed medium class PVC conduit, with piano type switch, phenolic laminated sheet, suitable size MS box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required. Group C.	115	Nos.		
2	Supply and fixing following piano type switch/socket on the existing switch box/cover including connections etc as required. (i) Switch 5 Amps. (ii) 3 pin 5/6 Amps. Socket out let.	33 Sets	E. set		
3	Wiring for light /power plug with 2x4 sq.mm. FR PVC insulated copper conductor single core cable in surface/recessed medium class PVC conduit along with 1 no. 4 sq.mm. FR PVC insulated copper conductor single core cable for loop earthing as required.	100 mtrs	P. mtr		
4	Supplying and fixing metal box of 180x100x60mm deep size (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc. as required.	3 Nos.	Each		
5	Supplying and fixing following piano type switch/socket on the existing switch box/cover including connections but excluding modular plated etc. as required. (i) Switch 15 Amps with 6 Pin socket out let 15 A	3 Nos.	Each		

6	Wiring for circuit/sub main wiring along with earth wire with the following sizes of FR PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required. (ii) 2x2.5 sq.mm. + 1x2.5 sq.mm. earth wire. (for circuit wiring and street light wiring)	600 mtrs	P. mtr		
7	Installation of exhaust fan up to 450 mm sweep in the existing opening, including making the hole to suit the size of the above fan, making good the damages connection, testing, commissioning etc. as required.	20 Nos.	Each		
8	Extra for fixing louvers/shutters complete with frame for an exhaust fan of all sizes.	20 Nos.	Each		
9	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board consumer unit, 240 volts, on surface/recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, hinged front acrylic cover for the MCB knobs, detachable gland plate, interconnections, phosphatised and powder painted including earthing as required (But without MCB/RCCB/Isolator). (i) 2+8way	5 Nos.	Each		
10	Supplying and fixing 63 Amp. rating, double pole, 240 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.	5 Nos.	Each		
11	Supplying and fixing 100 Amp rating, four poles, 415 volts, isolator with metallic MCB box complete with connections, testing and commissioning etc. as required.	1 Nos.	Each		
12	Supplying and fixing 5 amps to 32 amps, 240/415 volts, 'C' curve, miniature circuit breaker suitable for inductive load of single pole in the existing MCB DB complete with connections, testing and commissioning etc. as required. (single pole)	40 Nos.	Each		

13	Supply and installation of Polycarbonate flood light luminaire suitable for 65 Watt spiral Retro CFL RANGER 1 CFL Pressure die-cast aluminium floodlight luminaire for high Wattage Retrofit CFL. Lamp upto 65W Spiral CFL LHFC46165099 Retro (E27) along with 65W Spiral CFL complete as required (Havells make).	5 Nos.	Each		
14	Supply and installation of Weather proof, anti corrosion wall/ceiling mounted opel colour decorative, round shape engineering plastic housing with PC cover suitable for 1x20W Retro fit CFL model no. LHFHCFE1TL6W020 (on rolling shutter cantilever) Havells make.	10 Nos.	Each		
15	Supplying, installation, testing and commissioning of LED street light fitting with transparent, acrylic diffuser and aluminium canopy complete with all accessories duly wired and including supply of 1 No. 65/73 watt LED lamp etc. as required. (Street light: type 919515810008 BRP351 1xLLM1800/740 220-240V-50Hz SI 12500 Phillips make.	8 Nos.	Each		
16	Supplying and fixing of 32 mm dia x 2 mtr. Long GI pipe (medium class) bracket for mounting of fluorescent/HPMV/HPSV street light fitting on pole /wall including bending the pipe to the required shape, 2nos. 40mm x 3 mm flat iron clamp and wiring with 1.5 sqmm. PVC/WP wiring and painting the flat iron with primer and finishing paint as required.	8 Nos.	Each		
17	Installation, testing and commissioning of LED Street light fitting on the existing bracket including connection etc. as required. (on wall of seeds store)	8 Nos.	Each		
18	Supply of single phase Heavy duty 18"-1400 RPM exhaust fan complete with blades, frame and shutters etc. as required (GEC, Crompton/USHA make).	20 Nos.	Each		
19	Supplying of the following size of PVC insulated, PVC sheated 1.1 KV grade aluminium conductor armoured cable ISI mark. a) 2X10 sqmm. b) 3X10 sqmm.	200 mtrs 100 mtrs	P. mtr P. mtr		

20	Laying of 1 no. PVC insulated & PVC sheathed/ XLPE aluminum power cable of 1.1 KV grade of size not exceeding 35 sqmm direct in ground including excavation sand cushioning, protective covering & refilling the trench etc. as required. a) 2X10 sqmm. b) 3X10 sqmm.	25 mtrs 25 mtrs	P. mtr P. mtr		
21	Laying and fixing of 1 no. PVC insulated & PVC sheathed/XLPE aluminum power cable of 1.1 KV grade of size not exceeding 35 sqmm direct on wall/surface. a) 3X10 sqmm. b) 2X10 sqmm.	75 mtrs 225 mtrs	P. mtr P. mtr		
22	Providing and fixing 4 mm copper wire on surface or in recess for loop earthing alone with U.G. Cable as required (for DBS in seeds store & P.Plant)	350 mtrs	P. mtr		
23	Supplying and making end termination with brass compression gland and aluminium lugs for the following size of PVC insulated and PVC sheathed/XLPE aluminium cable of 1.1 KV grade as required. a) 3X10 sqmm. b) 2X10 sqmm.	2 sets 4 sets	E. set E. set		
24	Earthing with G.I. earth pipe 4.5 meter long, 40 mm dia (Medium class) including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal and salt as required.	2 Nos.	Each		
25	Providing and Laying earth connection from earth electrode with 6 SWG dia G.I. wire in 15 mm dia G.I. pipe from earth electrode, as required	15 mtrs	P. mtrs		
TOTAL Rs.					
Signature and seal of contractor					